

Folder 1134, Date 5-1914

Book: 1, Page: 27C

Dug at the $\frac{1}{4}$ corner of Sec. 3 on Tp. line between Tps. 1 and 2 South R. 26 E.W.M. found old charred post 20 inches beneath the surface, set temporary corner and surveyed S $00^{\circ} 01' W$ as per field notes, 39.82 chains set temporary corner and went east one half mile to $\frac{1}{4}$ corner between Secs. 2 and 3 Tp. 2 S.R.26 E.W.M. Dug in the center of the road and found piece of charred willow stake 20 inches beneath the surface as per the gov't field notes, re-established corner by setting stone 20x12x8 marked $\frac{1}{4}$ on east face, top of stone being set beneath the surface of the road about 4 inches, deposited charcoal under stone 30 inches beneath surface. Pits impracticable, being in center of the road. Beginning at said corner I surveyed S $89^{\circ} 40' W$ 40.08 chains as per field notes and intersected line previously established through the center of sec. 3. Set stone 20x9x8 marked C S on South for center corner of Sec. 3 Tp. 2 S.R. 26 E.W.M., thence returned to the $\frac{1}{4}$ corner of Sec. 3 on TP. line and dug hole 30 inches deep, deposited glass of broken brown qt. bottle and set stone 20x12x8 marked $\frac{1}{4}$ on East face and C S on South face for corner. Sec. 3 Tp. 2 SR 26

Loy M. Turner Co. Surveyor.

May 8 1914