

Corner to sections 4-5-8-9 Tp. 3 S R 25 E.W.M.

Found original stake laying on top of the ground at corner of sections 4-5-8-9 Tp. 3 S R 25 E.W.M., the four original pits were plainly visible. Dug and found point of stake. Re-established corner by digging pit 30 inches deep and deposited $\frac{1}{4}$ gallon of fine coal, and set stone 14-6-5- marked with 5 notches, on the South, 4 notches on the East and C S on the North. Redug the witness pits and built mound of earth around the stone also set original stake in mound.

Surveyed May 16 1914

Loy M. Turner Co. Surveyor.

Folder 1139, Date 5-1914

Book: 1, Page: 28E