

Folder 1140, Date 5-1914
Book: 1, Page: 28F-29A

Corner to sections 13-14-23-24 Tp. 2 S R 24 E.W.M.

Began at the $\frac{1}{4}$ corner between sections 14-23 Tp. 2 S R 24 E.W.M., thence S $89^{\circ} 48'E$ 39.74 chains, as per field notes, set temporary corner; began at the $\frac{1}{4}$ corner between sections 23-24, of said township, thence north 40.00 chains as per field notes, fell short of temporary corner by $\frac{1}{2}$ chain; began at the $\frac{1}{4}$ corner between sections 13-14, of said township, thence south 40.00 chains as per field notes, intersected east and west line 10

Folder 1140, Date 5-1914

Book: 1, Page: 28 F-29A

links east of temporary corner, divided distances and set original stone, which was found lying on top of the ground 100 feet distance, 40.25 chains North of the $\frac{1}{4}$ corner between sections 23-24 Tp. 2 S R 24 E.W.M. , and S $89^{\circ} 48' E$ 39.37 chains from the $\frac{1}{4}$ corner between sections 14-23 Tp. 2 S R 24 E.W.M. and being 6 feet North of the door of a cellar belonging to Arthur Keene, I deposited one pint of broken glass and burned nails under the stone. As the stone was real close to the house of Arthur Keene the pits were impracticable.

Surveyed May 17 1914.

Loy M. Turner Co. Surveyor.