

Survey of West Boundary of Sec. 19-25. 25 E.

Commencing at N.W. corner of Sec. 19, where I found orig. stone. I drove a $\frac{3}{4}$ " iron pipe along side of this stone. Thence southerly on random line. At 2627 ft. found old stone as described in notes. This stone was marked $\frac{1}{4}$ " & was 2 ft. west of my line. I built small cairn at this point and drove $\frac{3}{4}$ " inch iron pipe along stone. I continued my line on $\frac{1}{4}$ " at 5241 ft. came to stone crib where Mrs. Wm. Stauffer had maintained a fence ^{for 30 years} & where she had recollection of seeing the old stake & the pits before she had built the fence. I searched & dug diligently for old stake or charcoal but could find none. I therefore produced my line on and at 7869 ft. 14 ft. to the west, I found stone as described and to the 4 pits evidently dug more recently. I therefore went back on my line and at 5248 I offset 8 ft. West and established that point as the South West Corner of Sec. 19. where I dug a pit 15" deep and drove a $\frac{3}{4}$ " inch pipe about 22" long into the ground piled rock around it & recovered it as it was in the middle of a road. on the corner of the rock crib which is 8 ft. East I carved B.T. 8'

The establishment of this corner midway between the adjacent $\frac{1}{4}$ Cor. to the North & the adjacent $\frac{1}{4}$ Cor. to the South is the proper procedure as this corner lies on the township line and the Sec. line coming in from the East is not in line with the Sec. line coming from the West. Also it comes at the place where the evidence of Mrs. Wm. Stauffer would show that it was probably originally placed.

Surveyed June 15, 1920.

Caroline Steffen,
J. P. C. Murray.

See the next page For the transcribed copy of this survey.