

Re-established Corners Sec. 31 Tp. 1 S R 26 E.W.M.

At the corner to Tps. 1 & 2 S Rs. 25 & 26 E.W.M., I found traces of a mound with pits slightly discernable but the original stake had disappeared. I dug in the mound and found the rotten end of a fence post, but no trace of charcoal or other evidences of the original markings. I proceeded to re-mark the corner by setting a stone 30 x 12 x 8 in the center of the mound and re dug the pits, and built a mound over the stone. No marks were made on the stone.

I ran S 89°54'E 39.32 chains, as per gov't field notes, and set a post in mound for  $\frac{1}{4}$  corner. Marked post  $\frac{1}{4}$  on West side. No pits were dug owing to the fact that the corner is between two grain fields and would probably be plowed up in a short time.

From the  $\frac{1}{4}$  corner I ran North through the center of the section and at 20 chains I set an old piece of iron stove pipe in the ground for the corner to the NE  $\frac{1}{4}$  of the SW  $\frac{1}{4}$ , the SE  $\frac{1}{4}$  of the SW  $\frac{1}{4}$ , the SW  $\frac{1}{4}$  of the SE  $\frac{1}{4}$  and the NW  $\frac{1}{4}$  of the SE  $\frac{1}{4}$ ; at 40 chains I set a post in mound for the center of the section; at 60 chains I set a stone 16 x 6 x 4 for corner to SW  $\frac{1}{4}$  of NW  $\frac{1}{4}$ , NE  $\frac{1}{4}$  of the NW  $\frac{1}{4}$ , SW  $\frac{1}{4}$  of NE  $\frac{1}{4}$ , NW  $\frac{1}{4}$  of the NE  $\frac{1}{4}$ ; and at 80 chains intersected  $\frac{1}{4}$  corner between sections 31 and 30.

From the Tp. corner to Tps. 1 & 2 S Rs. 25 and 26 E.W.M. I ran North 20 chains and set stone for (40) corner; at 40 chains I set stone 12 x 10 x 10 for  $\frac{1}{4}$  corner between sections 31 and 36; at 60 chains I set stone 20 x 18 x 12 for (40) corner; at 80 chains I set stone 12 x 12 x 8 for corner to sections 25-30-31 and 36, in stone mound.

At the corner to sections 29-30 31 and 32 I found original stone in field of Frank Wilkins and set it 6 in. beneath the surface with broken glass of white beer bottle underneath, the corner being S 29° 39'W 2.80 chains from the SW corner of Frank Wilkin's house.  
(over)

Folder 1142, Date 10-1916

Book: 1, Page: 31A

From the corner to sections 29-30-31 and 32 I ran N  $89^{\circ}40'W$  40 chains as per gov't field notes and made stone mound for  $\frac{1}{4}$  corner between sections 30 and 31; at 60 chains I set stone 16 x 10 x 5 for (40) corner; at 79.30 chains I intersected section corner.

From the (40) corner, 20 chains North of the Tp. corner, I ran S  $89^{\circ}54'E$  19.32 chains and set stone 16 x 10 x 8 for corner to the NW $\frac{1}{4}$  of the SW $\frac{1}{4}$ , the SW $\frac{1}{4}$  of the SW $\frac{1}{4}$ , the NE $\frac{1}{4}$  of the SW $\frac{1}{4}$  and the SE $\frac{1}{4}$  of the SW $\frac{1}{4}$  section 31 Tp. 1 S R 26 E.W.M.

From the  $\frac{1}{4}$  corner between sections 31 and 36 Tp. 1 S Rs. 25 and 26 I ran S  $89^{\circ}47'E$  19.31 chains and set stone 14 x 10 x 5 for (40) corner.

From the (40) corner, S  $89^{\circ}40'E$  19.30 chains from the corner to sections 25-30-31 and 36, I ran South 20 chains and set stone 24 x 18 x 6 for corner to the NW $\frac{1}{4}$  of the NW $\frac{1}{4}$ , the SW $\frac{1}{4}$  of the NW $\frac{1}{4}$ , NE $\frac{1}{4}$  of the NW $\frac{1}{4}$  and the SE $\frac{1}{4}$  of the NW $\frac{1}{4}$  of section 31 Tp. 1 S R 26 E.W.M.

Surveyed Oct. 19-20 1916.

Loy M. Turner

Co. Surveyor.