

Tp 1 N R 26 E

Folder 1143, Date 3-1918
Book: 1, Page: 32A

Re-established Corners

At the quarter corner between sections 11 -12 Tp. 1 N R 26 E.W.M., I dug and found charcoal as per government field notes, no mound, stake or pits being visible, re-established corner by replacing the charcoal and planting a stone, of a pyramid shape, 15-10-4 inches, marked $\frac{1}{2}$ C.S. on West face, on top of the charcoal and built mound north of stone.

From the quarter corner between sections 11-12 Tp. 1 N R 26 E.W.M. I chained North 40.00 chains as per government field notes, dug and found rotted end of post but no charcoal, re-established corner by planting a stone 18-10-5 inches, marked with one notch on east face and one notch on south face and C.S. on top. The top of the stone is lowered one foot below the surface of the ground, being in the center of a county road.

March 20 1918.

At the corner to sections 1-6-31 and 36 Tps 1-2 N Rs 26-27 E.W.M., I dug and found rotted end of post and charcoal as per government field notes, no pits or mound being visible, nor any signs that there had ever been either mound or pits. I re-established the corner by replacing the charcoal and planting a stone 10-10-8 inches with barbed wire wrapped around it. Built a mound about the stone and dug pits as per requirements.

At the corner to sections 7-12-13 and 18 Tp. 1 N Rs 26-27 E.W.M., I dug considerable and found rotted end of fence post and charcoal as per government field notes, no mound or pits being visible owing to the fact the the land had been farmed nearby. I replaced the charcoal and planted a piece of strap steel 1/16 X 4 inches, doubled to three thicknesses, two feet long on top of the charcoal, built a mound about the steel and dug four pits, on the section lines to allow for farming.

From the corner to sections 7-12-13 and 18 Tp. 1 N Rs 26-27 E.W.M., I chained North 40.00 chains as per government notes, dug and found charcoal, no mound or pits being visible. I replaced the charcoal and planted a stone 14-10-8 inches with barbed wire wrapped around it on top of the charcoal, built a mound about the stone and dug two pits on the section to allow for farming.

March 20 1918.

Loy M. Turner

T 1 N R 26 E

Folder 1143, Date 3-1918
Book: 1, Page: 32B

Re-established Corners.

From the corner to sections 1-6-31 and 36 Tps 1-2 N Rs 26-27 E.W.M. I chained South 80.00 chains as per government field noted and set temporary stake for corner to sections 1-6-7-12 Tp. 1 N Rs 26-27 E.W.M., thence From the corner to sections 7-12-13-16 Tp. 1 N Rs 26-27 E.W.M. I chained North 80.00 chains as per government field notes and fell short of the temporary stake by 43 links. Dug up considerable ground but could find nothing of original stake or charcoal, but found the rotted ends of three fence posts at a point midway between the two temporary stakes. At this point I dug a hole 3 feet deep and deposited a quart of broken glass and china ware also a cast iron gear pinion 4 inches in diameter, planted a stone 20-16-6 inches marked with one notch on south face and C.S. on east face. The top of the stone is one foot below the surface to provide for a county road.

From the corner to sections 1-6-7-12 Tp. 1 N Rs 26-27 E.W.M. I chained West 39.85 chains as per government field notes and planted a stone 14-8-4 inches marked $\frac{1}{4}$ C.S. on South face for corner between sections 1-12 Tp. 1 N R 26 E.W.M.

March 21 1918.

From the corner to sections 1-2-11 and 12 Tp 1 N R 26 E.W.M. I chained West 39.75 chains as per government field notes and set stone 16-8-6 inches marked $\frac{1}{4}$ C.S. on west face for quarter between secs 2-11 Tp. 1 N R 26 E.W.M. Set top of stone one foot below surface to provide for a county road.

At the corner to sections 2-3-10-11 Tp. 1 N R 26 E.W.M. I set stone 16-10-5 marked with two notches on east face and one notch on south face, also C.S. on west face built small mound about stone but pits were impracticable.

March 22 1918.

Loy M. Turner
C.S.