

At quarter corner between sections 4-33 Tps. 3-4 S R 24 E.W.M., I set stone 20-10-5 inches marked $\frac{1}{4}$ on South face and C.S. on East face. Set stone in road 8 inches below surface.

Nov. 12, 1918. At quarter corner between sections 32-5 Tp. 3-4 S R 24 E.W.M., I set stone 12-6-5 inches, marked $\frac{1}{4}$ on South face and C.S. on top. Set stone in road 8 inches below surface with quart of fine coal underneath, set witness stone 14-10-10 inches under fence 70 links West.

At corner to sections 32-33-4-5 Tps. 3-4 S R 24 E.W.M., I set stone 14-10-8 inches, 10 inches beneath surface, marked 6 notches on South face and 4 notches on the East face, C.S. on top, placed quart of coal under stone and set witness stone 53 links South.

Nov. 13, 1918. At corner to sections 21-22-27-28 Tp. 3 S R 24 E. W.M., I set stone 18-16-8 inches marked with two notches on the South face and 3 notches on the East face, C.S. on the South, placed quart of coal around stone.

At the quarter corner between sections 21-22 Tp. 3 S R 24 E.W.M., I set a stone 16-8-6 inches marked $\frac{1}{4}$ on East face and C.S. on South face, place quart of coal under stone.

Nov. 14, 1918. At corner to sections 16-17-20-21 Tp. 3 S R 24 E.W.M., I set a stone 20-16-8 inches marked with 3 notches on the South and 4 notches on the East face, C.S. on the northwest face, placed quart of coal around the stone.

Nov. 15, 1918. At quarter corner between sections 20-21 Tp. 3 S R 24 E.W.M., I set a stone 16-10-8 inches marked $\frac{1}{4}$ on South and C.S. on East face, placed quart of coal around stone.

At corner to sections 20-21-28-29 Tp. 3 S R 24 E.W.M., I set a stone 14-8-6 inches marked with 2 notches on South face and 3 notches on East face and C.S. on Northeast face, placed pint of coal under stone.

Folder 1144, Date 11-1918

Book: 1, Page: 35B