

Re-established corners.

1 From the $\frac{1}{4}$ corner between sections 28 and 29 Tp. 1 S R 23 E.W.M., I ran North 40.00 chains and set stone 20x8-6, with pedestal on bottom, 16 inches in the ground, and marked with 4 notches on South and 4 notches on West, and CS on South for corner to sections 20-21-28 and 29 Tp. 1 S R 23 E.W.M.

2 Thence North 39.81 chains and set stone 12x10x7, 8 inches in the ground, marked $\frac{1}{4}$ on South and CS on East for corner between sections 20-21 Tp. 1 S R 23 E.W.M., pit impracticable being in the center of county road.

3 At the $\frac{1}{4}$ corner between sections 29-30 Tp. 1 S R 23 E.W.M. I dug and found end of rotten fence post. A farmer, who had maintained the fence for several years, vouched that the place was the exact location of the original government corner, which was until a few years ago marked by a stone, but at this time no stone could be found. I re-established the corner by setting a stone 16x7x6 marked $\frac{1}{4}$ CS on West with mound along side, in the center of county road.

4-5 I then ran North 40.00 chains, through a grain field belonging to Willard Blake, and could find no trace of the original corner, set temporary corner, and ran East 79.66 chains to the corner of sections 20-21-28 and 29, thence S $89^{\circ}31'W$ 39.83 chains, set stone 16-12-8, marked $\frac{1}{4}$ on south, on south slope of rocky hillside, for $\frac{1}{4}$ corner between sections 20 and 29, thence continued S $89^{\circ}31'W$ 39.83 chains to section corner, where I re-established the corner by setting a stone 16-12-5, marked 4 notches on South and 5 notches on East and CS on top, the corner being in a grain field I set the stone 16 inches beneath the surface, the place being 1.05 chains West from the bottom of a small ravine.

Loy M. Turner
Co. surveyor.

June 19-20-'16.