

Folder 1146, Date 6-1914

Book: 1, Page: 34A

Re-established corners on the South and East sides of section 14 Tp. 1 S R 27 E.W.M.

At the  $\frac{1}{4}$  corner on the south side of section 14, I found a mound of earth with slight depressions on the south and north at about 8 links distance. I dug on all sides of the mound but could find no trace of the original government  $\frac{1}{4}$  stake, and I re-established the corner by setting a stone 12x5x4 inches, marked  $\frac{1}{4}$  on the west face, on the west side of the mound. I also redug the pits and put the earth on the mound making it more prominent.

From the supposed corner to sections 13-14-23 and 24, I ran North 40 chains as per field notes and arrived exactly on top of a small mound of earth with slight depressions on the east and west at about 8 links distance. Upon digging I found only the charred end of a cedar post about 2 ft. under the surface. Being quite satisfied that the place was the exact location of the original gov't corner, I re-established the corner by planting about  $\frac{1}{2}$  gallon of broken pieces of a white earthenware jug, 18 inches under the surface and on top of that I set a tamarack pole 4 inches in diameter, which extended about 4 ft. above the surface. I marked  $\frac{1}{4}$  CS on the west side of the pole. Re-dug the pits and built an earth mound around the pole.

Surveyed September 27, 1916.

Loy M. Turner  
Co. Surveyor.