

Re-established corners.

Nov. 11, 1918.

At the corner to sections 3-4-33-34 Tp. 3-4 S R 24 E.W.M., I set a stone 16-8-6 inches, average 3 inches square on top, marked 6 notches on the South and 3 notches on the East face, C.S. on South face. Top of stone is 8 inches below surface, being in road, planted quart of fine coal around stone.

At quarter corner between sections 4-33 Tps. 3-4 S R 24 E.W.M., I set stone 20-10-5 inches marked $\frac{1}{4}$ on South face and C.S. on East face. Set stone in road 8 inches below surface.

Nov. 12, 1918. At quarter corner between sections 32-5 Tp. 3-4 S R 24 E.W.M., I set stone 12-6-5 inches, marked $\frac{1}{4}$ on South face and C.S. on top. Set stone in road 8 inches below surface with quart of fine coal underneath, set witness stone 14-10-10 inches under fence 70 links West.

At corner to sections 32-33-4-5 Tps. 3-4 S R 24 E.W.M., I set stone 14-10-8 inches, 10 inches beneath surface, marked 6 nothes on South face and 4 notches on the East face, C.S. on top, placed quart of coal under stone and set witness stone 53 links South.