

SURVEY OF THE NORTH LINE
OF
THE SOUTH HALF OF THE SOUTH HALF
OF

Sec. 24, T. 1 N. R. 27, E. W. M.

Went to the Southwest corner of Sec. 24 which I identified by stone marked as described by Loy Turner, C. S. in his survey of March 1919. Searched but could find no sign of the 1/4 corner but did find an established 1/16 corner 20 chains South of a mound of rocks which I accept as the Northwest corner of the section.

Went to the Southeast corner of the section and found a mound of rocks, but no identifying marks. From this mound I run North and find an old blazed willow or juniper post in mound of rocks as described by the field notes. This post is about 150 feet West of the present fence. From the 1/4 corner I run South 20.00ch. and set flag.

Went to the Southwest corner of the section and ran North along the section line 20.00 ch. and set stone marked 1/16 corner. From this 1/16 corner I run Easterly on the line of the corner and flag and set stakes for fence line as far East as the county road.

H. Tamblyn
County Surveyor.

Apr. 10, 1940

Folder 1149, Date 4-1940

Book: 1, Page: 36A