

Re-established Corners  
Sections 25-26 Twp. 1 N R 27 E.T.M.  
March 26-27 1919.

Folder 1151, Date 3-1919

Book: 1, Page: 366

At the corner to sections 26-27-24 and 35 I dug in small mound and found charcoal and end of rotten stake, set stake in hole with the charcoal and redug the 4 pits making mound around the stake.

At the  $\frac{1}{4}$  corner between sections 26-35 I dug in small mound and found charcoal, set a stone 16 X 10 X 8 inches, no marks on the stone, dug pits on north and south of stone and raised mound around the stone.

North 40.0 chains from the corner to sections 26-27-34 and 35, I planted  $\frac{1}{2}$  of a buggy axle 30 inches long, with the thread end up, and set the upper end 6 inches beneath the surface, set a witness corner South 25 feet on the bank of Butter creek, said witness corner being a thimble and boxing of a three inch wagon, No pits since the corner is in an alfalfa field.

At the corner to sections 22-23-26 and 27 I dug in small mound and found charcoal, set a stone 24-8-6 inches, no marks on the stone, dug 4 pits and raised mound about the stone.

At the  $\frac{1}{4}$  corner between sections 23-26 I dug in small mound and found charcoal, set a post 6 inches in diameter and dug pits on the east and west of post and raised mound about post. (Note: the pits should have been on the north and south of the post.)

At the corner to sections 23-24-25 and 26 I dug in small mound and found much charcoal, set a stone 16-6-4 inches marked with 4 notches on the south and 1 notch on the east, C.S. on south face, dug 4 pits and raised mound about stone.