

Re-established Corners

Jan. 28, 1919. From the corner to sections 19-20-29-30 Tp. 1 N R 27 E.W.M., I ran N $89^{\circ}59'W$ 40.00 chains, as per gov't field notes, dug in a small mound and found charcoal. Set a stone in the mound, 16-12-8 inches no marks on it. Dug pits on the South and North.

Continued west on the same bearing 45.50 chains as per field notes, but found no trace of original corner since the land was plowed. Set temporary corner. From the Tp. corner on the Base Line I ran North on the Tp. line 2 miles and 25 feet to temporary corner. From the corner to secs. 7-12-13-18 on the Tp. line I ran South 2 miles and 8 feet to temporary corner. Set a stone 18-12-8 inches marked with 6 notches on East and West and 2 notches on the South also C.S. on South, at the temporary corner with 1 quart of coal under stone, for corner to secs. 19-24-25-30 Tp. 1 N Rs 26 & 27 E.W.M.

West 40.00 chains from the corner to secs. 19-24-25-30, I dug and found the original charcoal in a plowed field, set a stone 14-6-5 inches, marked $\frac{1}{4}$ on South and C.S. on East.

At the corner to secs. 29-30-31-32 I dug and found the original charcoal, set a stone 18-12-9 inches marked 5 notches on East and 1 notch on the south, built mound about stone and dug pits as per instructions. Tp. 1 N R 27 E.W.M.

Folder 1155, Date 1-1919

Book: 1, Page: 38A