

Re-established corner to sections 17-18-19-20 Tp. 4 S.R. 28 E.W.M.

At corner to sections 17-18-19 and 20 I found the original stake rotted off and lying in a mound of stones adjacent to the bearing trees as described in the field notes, and proceeded to re-establish the corner by setting a stone 10 x 8 x 5 inches marked 17 and 18 on the northeast and northwest respectively also marked 19 and 20 on the southwest and southeast respectively, and also marked C S on the south side. Said stone was set in the center of the mound of stones and the mound made larger. Oct. 15 1914.

Re-established corner to sections 7-8-17 and 18 Tp. 4 S.R.28 E.W.M.

Approached the corner to sections 7-8-17 and 18 and found trees as described in the original field notes as the bearing trees but the marks were completely grown over and one could detect only a small scar where the scribes were made. After cutting about 4 inches into the trees the original scribes were revealed, proving that the trees were the original bearing trees. After searching for some time among much undergrowth the original stake as described in the fieldnotes was found rotted off and almost covered with dead twigs and leaves, nearby was found the the end of the stake in the ground, proving the corner. I re-established the corner by planting a stake(as no suitable ^{stone} could be found at a convenient distance) 24 inches long and 4 inches square marked 7 and 8 on the northwest and northeast and 17 and 18 on the southeast and southwest, in the hole from which I removed the rotten end of the original stake, also built a mound on small stones around the stake. Oct. 14 1914.

Folder 1156, Date 10-1914
Book: 1, Page: 39A

Sept. 22 1914. Corner to 17-18-19 and 20. Tp. 1 N.R.27 E.W.M.

1117

From the corner to sections 16-17-20 and 21 I ran West 40.00 chains and dug over a considerable area of ground ^{could} but find no trace of the $\frac{1}{4}$ corner between sections 17 and 20, continued west 41.07 chains and found, by digging, a deposit of charcoal and the rotten end of a willow stake this was beyond doubt the original corner and I re-established it by setting a stone 16x7x7 marked C S on the west face, over the spot where I found the portion of stake and charcoal deposit, built an earth mound around the stone and dug 4 pits as per instructions 14 links from the stone. Deposited a large necked olive bottle in the SE pit and catsup bottles in the other three pits. ($\frac{1}{4}$) Rechaind East 40.53 chains and after considerable digging I found a deposit of charcoal and the rotten end of a stake which marked the place of the original $\frac{1}{4}$ corner between secs. 17 and 20. I re-established