

the corner by setting a stone, over the spot where the charcoal deposit was found, 16x8x5 marked $\frac{1}{4}$ on the south and C S on the East, over the spot where the charcoal deposit was found, and dug pits on the section line 14 links from the stone. Deposited a catsup bottle in the west pit and a $\frac{1}{2}$ gallon honey can in the east pit.

From the corner to sections 17-18-19 and 20 I ran South 40.05 chains, dug over considerable ground and found deposit of charcoal and rotten end of stake, the original $\frac{1}{4}$ corner between sections 19 and 20^I are-established the corner by setting a stone 12x10x 5 marked $\frac{1}{4}$ on east face and C S on the top, over the spot where was found the deposit of charcoal. Built earth mound around the stone and dug pits on section line 7 links from the stone and deposited a red brick in each of the pits. Continued South 40.05 chains and after digging ~~only~~ over a small area found a deposit of charcoal and the rotten end of a stake, marking the spot of the original corner to sections 19-20-29 and 30 Tp. 1 N.R. 27 E.^W.M. Re-established the corner by setting a steel plow, both stem and mole board marked C S on the East side and near the top of the stem, raised earth mound around the plow and dug pits as per instructions 7 links from the corner depositing stones, tin pans, sheet iron, and wire in the pits, also planted a portion of the broken wooden plow beam in the mound by the side of the plow. Ran East 40.59 chains, dug and found deposit of charcoal and rotten end of willow stake which marked the spot of the original $\frac{1}{4}$ corner between sections 20 and 29, re-established the corner by setting a willow post 4 inches in diameter and a small stone marked $\frac{1}{4}$ on SE face and C S on NW face, over the spot where I found the deposit of charcoal, raised earth mound around the post and dug pits on the section line and deposited small stones in each of the pits.

Sept. 22 1914.

Folder 1157, Date 9-1914
 Book: 1, Page: 39B