

Re-established Corners.

At the  $\frac{1}{4}$  corner between sections 1-6 Tp. 2 N Rs 25 & 26 E.W.M., I found an old earth mound, but no stake or pits were visible. I dug in the mound and found a small amount of charcoal as described in the gov't field notes. Being satisfied that this was the location on the original corner I proceeded to re-establish the corner by planting a post 4 inches square exactly in the place where the charcoal was found, also replaced the charcoal, dug pits on the East and West of the post and re built a mound about the post.

Wednesday Nov. 15 1916.

At the corner to townships 2 & 3 N Ranges 25 & 26 E.W.M. I found an old earth mound at which there were no stake or pits visible. I dug in the mound and found the rotted end of a willow stake and small pieces of charcoal as per Gov't field notes. Re-established the corner by replacing the charcoal and planting a post over the charcoal and dug pits on the NE, SW, NW, and SE of the post, also built a mound about the post.

Wednesday Nov. 15 1916.

At the corner to sections 1-2-35-36 Tps 2 & 3 N R 25 E.W.M. I found an old mound at which the pits were slightly visible. Re-established the corner by planting a post in the mound, digging pits as per gov't instructions and building a mound about the post.

Wednesday Nov. 15 1916.

Folder 1159, Date 11-1916

Book: 1, Page: 41A