

Folder 1160, Date 11-19-16

Book: 1, Page: 41B

At the corner to sections 11-12-13-14 Tp. 3 N R 25 E.W.M. I found a mound with pits slightly visible, and after digging in the mound I found the rotted end of a willow stake. I re-established the corner by planting a post 4 inches square at the exact place where I found the end of the stake, redug the pits and made a mound about the post.

Thursday Nov. 16 1916.

At a point East 40.00 chains from the corner to sections 11-12-13 and 14 Tp. 3 N R 25 E.W.M. I found the original $\frac{1}{4}$ stake lying on top of the ground, but there was nothing visible to mark the spot of its original location as the soil was sandy and there were signs of much change by wind storms. Consequently I established a corner by planting a post 4 inches square and dug pits on the North and South of the post and built a mound about the post.

Thursday Nov. 16 1916.

At a point 40.00 chains South of the corner to sections 11-12-13-14 Tp. 3 N R 25 E.W.M. I found no trace of the original $\frac{1}{4}$ corner as the place was in a sand blow. I established a corner by planting an old fence post, dug pits on the East and West and built a mound about the post.

Thursday Nov. 16 1916.

At a point 80.00 South of the corner to sections 11-12-13-14 Tp. 3 N R 25 E.W.M. I found no trace of the original section corner. I established a corner to sections 13-14-23-24 by planting a fence post, digging pits as per instructions and building a mound about the post.

Thursday Nov. 16 1916.

Loy M. Turner
Co. Surveyor.