

Field Notes Of H.W. Fells Survey

c

C Starting at the s.E. corner sec. 12 Twp. 5.S. R. 26.E. W.M. thence N.  $21^{\circ}30'$  40 ch. sec. found rock had been moved 40 links w.  $45^{\circ}$  E. under an old log fence

I set a new rock on true line buried a McCormick mower guard under it and cut C.S. on rock marked B.T. 2.02 ch. N. and 3. links E. of true line

thence N.  $21^{\circ}30'$  E. to cor. I. and I 2 40 ch. thence N.  $21^{\circ}30'$  E. 40 ch. set temporary  $\frac{1}{4}$  cor. thence N. 40 ch. to twp. cor. south on true line 40 ch. set permanent  $\frac{1}{4}$  cor.

buried mower guard point N.W. set rock 13x15x18 in. marked  $\frac{1}{4}$  s. cs. S.  $21^{\circ}30'$  E.

20 ch. Set rock for I 6 cor. thence W. 20 ch. dug pit set rock marked  $\frac{1}{4}$  W. W.

on true line 20 ch. set rock marked  $\frac{1}{4}$  and built mound W. 20 ch. on true

lines set rock marked  $\frac{1}{4}$  W. 20 ch. intersect sec line I.2 set rock marked

$\frac{1}{4}$  buried the jaw of an iron vise . B.T. S.  $60^{\circ}$  E. 40 links thence N. 20 ch

where I sent a flag E. to  $\frac{1}{4}$  cor on range line between sec. I and 6 Twp. 5 s R. 26 &

27 E.W.M. Var.  $20^{\circ}$  E. Thence W. on True line 40 ch. where I dug pit put mower

in bottom placed rock on top marked  $\frac{1}{4}$  thence N.  $21^{\circ}30'$  E. 20 ch. dug pit 12 in. *Guard*

deep put mower guard in bottom placed rock on top 18x8x6x9 in. marked  $\frac{1}{4}$

thence W. 20 ch. dug pit set rock 15 x 15 x 14 in. marked  $\frac{1}{16}$  thence N. 20 ch

intersect Twp <sup>link</sup> 4 & 5 S. R. 26 E.W.M. set rock in ground 9 x 17 x 14 In. marked

--I-- From here I went E. to  $\frac{1}{4}$  cor. between I & 36 and chained W. 40 ch.

Folder 1165, Date 10/12/1907

Book BK 2, Page 2

27 E.W.M. Var. 20° E. Thence W. on True line 40 ch. where I dug pit put mower *Guard*  
in bottom placed rock on top marked I-- thence N. 21°30'E. 20 ch. dug pit I2 in.  
deep put mower guard in bottom placed rock on top 18x8x6x9 in. marked--I--  
thence W. 20 ch. dug pit set rock 15 x 15 x 14 in. marked  $\frac{1}{16}$  I-- thence N. 20 ch  
intersect *line* Twp 4 & 5 S. R.26 E.W.M. set rock in ground 9 x 17 x 14 in. marked  
--I-- From here I went E. to  $\frac{1}{4}$  cor. between I & 36 and chained W 40 ch. I found the  
cor. of I & 2 had been destroyed and after taking what evidence I could and  
running a line into it four ways I dug pit 2 $\frac{1}{2}$  feet deep put 36 rock a horse  
shoe and a mower guard in bottom filled up with soil set a rock on top marked  
<sup>48</sup>  
---26--- on N. side 5 on S. I on E. & IIIII on the west side thence W. on true  
line 40 ch. I found the  $\frac{1}{4}$  cor had been obliterated after making thorough search  
I dug pit put a tin can containing a copper cent date 1906 .one peice of brass 1 $\frac{3}{4}$  x  
2 in. and a small peice glass in bottom filled pit with soil set rock marked  $\frac{1}{4}$  C.S.  
on top thence S. 20 ch. set rock marked I 1/16 on top C.S on on W Side  
thence E. 20 ch. on true line set rock marked --+-- thence E. on true line 20 ch. intersect  
sec. line between I & 2 20.10 ch. S of sec cor I & 2 on Twp. line Thence S. 20.28 ch.  
on True line between I & 2 TO  $\frac{1}{4}$  cor. I found the old *gmnt.* cor had been nearly  
obliterated and after chaining 3 ways I set a rock on the old mound marked  $\frac{1}{4}$  S with C.S.  
on the N. side. W. from  $\frac{1}{4}$  cor 60 ch. set rock for 1/16 cor. S. 20 ch built mound of rock  
for cor. marked one *XV-9-7-07*

Chairmen. Oscar Davis, Loyd Fell

Rodman. H.W. Fell

Surveyor. V.H. Heath

Recorded October 12<sup>th</sup> 1907