

Field notes of the survey
of Browns addition to the Town of Heppner Morrow County Oregon

C

Commencing at an oak stake driven firmly in the ground 11 feet and 10 inches east of the north east corner of Elder street as the same now appears on the recorded plats, thence running east 318 feet, thence north 132 feet thence West 318 feet, thence south 132 feet, to place of beginning: making the exterior of the south $\frac{1}{2}$ of block one of said addition said south half said block one I of said addition I have divided in to five lots numbered from 1 to 5 inclusive, such lots 1 to 4 inclusive being each 66 feet in width and 132 feet in length and said lot 5 being 54 feet in width and 132 feet in length.

Then commencing at a point 11 feet and 10 inches north of the north east corner of lot 12 of block 3 of Quaid's addition to the city of Heppner, thence running east 60 feet, thence east 313 feet, thence north 132 feet, thence west 313 feet thence south 132 feet to place of forming the exterior of the north half of block one of said addition.

said north half of block one I have divided in to five lots numbered from 6 to ten inclusive lot 6 being 49 feet in width and 132 feet in length and lots 7 to 10 inclusive being 66 feet in width and 132 feet in length. Then starting from the same point 22 feet and 10 inches north of the north east corner of lot 12 of block 3 of Quaid's addition to the city of Heppner, Oregon, thence running west 132 feet thence north 132 feet thence east 132 feet thence south 132 feet to place of beginning, being the exterior of block no. 2 of said addition. said block no. 2 I have divided in to two lots numbered 1 and 2 each being 66 feet in width and 132 feet in length Aiken street on the south of said block 1 as platted, is 50 feet in width, Brown street on the north of blocks 1 and 2, as platted is 50 feet in width, Elder street as shown on the plat is 60 feet in width; the alley running through the center of block 1 and the alley along the south side of block 2 as platted are each 12 feet in width. and the alley running along the west side of Kliens Tract as shown on the plat is 16 feet in width.

V. H. Heath, County surveyor

Morrow County Oregon.

Folder 1166 Date 10/1907

Book: 2 Page: 3