

S. P. Devin Survey

Commenced at the N.W. corner of Section 16 Tp. 4S, R 28 E, T. 1M.

Thence N. 20 ch. Marked Pine 4 in. diam.  $\frac{1}{8}$  S. C. S. B.T.

Thence East 20 ch. A rock 20X18X12 marked with a cross, marked pine tree 8 in. diam.  $\frac{1}{8}$  S. C. S. B.T.

Thence North 20 ch. along line of old blazes. Marked white fir tree 18 in. diam.  $\frac{1}{8}$  S. C. S. B.T. blazed on four sides for corner.

Thence West 20 ch. Drove stake, marked small fir 6 in. diam.  $\frac{1}{4}$  S. C. S. B.T. Fir 4 in. diam.  $\frac{1}{4}$  S. C. S. B.T.

Thence North 37 ch. Spring Branch. Dead fir 12 in. diam. having old blaze on it for line tree. 38 ch. Willow Creek. 40 ch. to where corner ought to be. Could not find any trace of original corner. Found blazes running east and having come north on original blazed line set corner at intersection of blazed lines running north and east. for the N.E. corner sec. 8 or corner to secs. 4, 5, 8 & 9 Tp. 4S, 28 E.

Drove stake marked C.S. from which a Bull Pine 6 in. diam. bears N.  $21^{\circ}-30'$  W. 10 lks, scribed S. 5 C. S. B.T. A Bull Pine N.  $89^{\circ}-36'$  W. 31 lks. scribed S. 5 C. S. B.T. A Bull Pine N.  $53^{\circ}-15'$  E. 53 lks. A Bull Pine S.

$23^{\circ}-05'$  W. 1.75 ch. scribed S. 8 C. S. B.T.

Sep. 12-1908.

D. V. J. Reid - County Surveyor.