

E. J. Hammer - Survey

Commenced at the  $\frac{1}{4}$  corner between sees. 10 & 11 <sup>2 1/2</sup> Tp. 1 S. R. 24 E. N. W. Thence West 40 ch. to the corner to sees. 2, 3, 10 & 11. Found no evidence of the corner excepting the corner post to fences running west and north. This post has been the accepted corner for many years and I therefore set a rock 18x10x8 marked C. S. for the corner, it being in the north line of E. J. Hammer's land.

Thence west 20 ch. to Hammer's N. W. corner. The corner falls in Hills low Creek. Set line stakes N. & N. of corner and south on S. side of creek and on hill south for Hammer's N. line.

Returned to cor. to sees. 2, 3, 10 & 11 Thence south 20 ch. and at 20 ch. set temp. 40 corner. 39.60 ch. to  $\frac{1}{4}$  corner between sees. 10 & 11. which is a rock in a rock mound. Returned north 39.20 ch to Hammer's south line and set the temp. 40 corner north 20 lks.

Set permanent corner a rock 12x10x8 for corner.

Thence east 16 ch. to Hammer's S. E. corner. Drove stake made deposits of charcoal 10 lks N. E. N. W, SW & S. E. as witnesses

Thence N. 20 ch. Set post for Hammer's N. E. corner  
Thence West 16 ch. to cor to sees. 2, 3, 10 & 11. Tp. 1 S. 24 E.  
Mar. 3<sup>rd</sup> 1909

D. V. J. Reid - Co. Surveyor.