

Robert Dexter - Survey to sell J. L. Wilkins tract.

Commencing at S.W. corner Sec. 35 T₂S. R. 26 E. W. M.

Thence east, 40 ch. set temp $\frac{1}{4}$ corner, 80.04 intersect N. + S. line 2 lks S. of corner which is marked by a rock. The correction for the temp. $\frac{1}{4}$ cor is therefore E. 2 lks and N. 1 lk, which correction I made and drove crow bar 36 in. & filled hole with fine charred stone coal, for the quarter section corner on the south side sec. 35 T₂S. R. 26 E. The center of Pat Barry's well bears S. $37^{\circ}00'$ E. 64 lks. The N. E. corner Pat Barry's main part of house bears N. $85^{\circ}50'$ W. 1.33 ch.

From the above described quarter section corner draw west 2.10 ch. to the center of County road up Balm Fork. Thence around Levi Hanfords & A tract as follows; West 7.25 ch. Drove stake for Hanfords & J. L. Wilkins corner. North 7 ch. Drove stake for Hanford & Wilkins cor. Thence E. 7.64 ch. to center of County Road up Balm Fork. Drove stake for Hanfords N. E. cor and Wilkins S. E. corner. Thence N. $11^{\circ}54'$ E. along center of county road 9.22 ch. Drove crow bar 30 in. Deposited charred stone coal and drove stake 11 ft. from sign post at forks road. Thence N. $37^{\circ}03'$ W. 5.50 ch. Drove crow bar and deposited charred stone coal for Wilkins N. E. corner in County Road.

April 17-1909.

D. V. F. Reid - County Surveyor.