

R. Hoogeland - Survey.

At the S.W. cor. Sec. 14 T₄S, R. 26 E., Found bottom of stake.
Set rock 20x8x3 marked C.S. for corner, from which Yellow Pine 36 in.
diam. bears N. 90° W. with old blaze on it, presumably for witness
tree, also marked on E & W sides for line tree which. Also Yellow Pine
due South marked as line tree and in line with two other trees south
marked as line trees. From this corner a yellow Pine 32 in. diam. S.
161 lks. Red Fir stump 30 in. diam. N. 69° E. 188 lks. Red Fir Tree 30 in.
diam. N. 69° 30' E. 200 lks.

Thence East, 40 ch. $\frac{1}{4}$ corner on S. side Sec. 14 - 55, 26 E. Thence
North 20 ch. Set Stone for corner from which Y. Pine N. 89° 30' W. 57 lks.
Thence West, 20.13 ch. Set rock marked C.S. for corner from which
Red Fir 20 in diam S. 45° W. 14 lks. Y. Pine East 19 lks.
Thence South, 20 ch. to sec. line at stone set as described above.

May 29 - 1909.

D. V. Reid - County Surveyor.