

James Reid and Vaughn - Survey

Commenced at  $\frac{1}{4}$  cor. bet. secs. 7+18 T<sub>1</sub>P. 55, R. 27 E. a rock and witness trees for  $\frac{1}{4}$  corner. Jas Reid says on former survey it was found that this corner is 40 ch. and a few links from S. E. cor sec. and 37.50 ch from S. W. corner sec. 7. Ran North 80 ch. Found no trace of corner or witness trees. Ran East, 41 ch. intersect N. + S. line 73 lks. South of Sec. corner. Returned to N. side Sec. 7-55-27 E. and set over 1 chain East and 28 lks. South and set rock 18X10X2 marked  $\frac{1}{4}$  C.S. in mound of rock for quarter section corner between secs 6+7 T<sub>1</sub>P. 55 R 27 E. from which, Yellow Pine 30 in. diam. N.  $35^{\circ}-30'$  W. 42 lks. Bull Pine 18 in. diam. S.  $25^{\circ}-15'$  W. 43 lks. Trees marked  $\frac{1}{4}$  C.S. B.T. This corner stands on slope  $31^{\circ}$  to W. about 100 yards above + Coofthom Creek across which to the west is an unsurmountable mountain or precipice. Therefore did not run west to prove location of this corner

Sep. 4-1909

D. V. J. Reid - Co. Surveyor.