

# Mike Marshall - Survey

Commenced at N.E. corner sec. 25 T<sub>1</sub>S. R. 23 E. Thence South 97° 8' W. 40.11 ch. 1/4 cor stake on top ground, 71.59 ch. Stake set by Pendleton surveyor for sec. corner. 80.56 point where Marshall claims corner.

At 80 ch. set temp. cor stk. for S.E. cor sec 25. 120.56 ch. 1/4 corner rock 47 lks to East - a white like rock on top apparently round & resembling rocks found over portions of this country believed to have been carried here in icebergs during past ages, marked

1/4. Returned to S.E. cor sec 25. Set temporary stake over 35 3/8 lks E. and 36 lks S. Set post scribed C.S. and rock 14x10x8 alongside marked C.S. and made four deposits, <sup>10 ex. dist.</sup> S.W. broken glass bottle, N.W. stone coal and charcoal N.E. & S.E. Stone coal & charcoal. The

post above referred to as set at 71.59 ch. by Pendleton surveyor is said to have been set by surveyor Macomber and bears N. 1° 37' W.

8.75 ch. Davis & Bushee were his chainmen and probably jabbed him in an effort to drive Marshall off his range. Mr. Dader Cabin S. 72 E. about 10 or 12 ch. Marshall's corner 5 ch. E. & 2.52 ch. S. from the established S.E. cor sec 25 T<sub>1</sub>S. R. 23 E.

Apr. 30 - 1910

D. V. J. Reid - Co. Surveyor.