

N. G. Scott - Survey

Commenced at S. W. cor. Sec. 36 T<sub>1</sub> S. R. 25 E. N. W. Dug and found point of original government stake. Dug hole 2 ft. deep, set steel wagon skin and rock against it 18X7X2 in. marked C.S. for corner, made four references of deposits of charred stone coal 10 lks. dist. from corner from surface down 30 inches N. E., N. W., S. W. & S. E.

Thence North. 40 ch set temp  $\frac{1}{4}$  corner. Dug for remains of stake but found none. 80 ch. set temp. cor stk. Found no trace of corner. 120 ch. No trace of corner. 160.08 ch. 10 lks E. of N. W. cor Sec. 25 a mound & rock.

Returned to N. W. cor sec 36, set temporary stake S. 4 lks and N. 5 lks. Dug hole 2 ft deep, set steel wagon axle skin for corner. Made four references of deposits of charred stone coal 10 lks distant from corner N. E. N. W. S. W. & S. E. from surface down 30 inches, for corner to secs 25, 26, 35 & 36 T<sub>1</sub> S. R. 25 E. N. W. and for Scott's N. W. Corner.

Thence West. 40 ch. found the government rock set to mark the quarter section corner on the N. side sec. 36 of said T<sub>1</sub>. Thence E. 20 ch. set rock marked C.S. for corner. Thence South, 20 ch set corner. Thence West 40 ch. set corner for the S. W. cor N. E.  $\frac{1}{4}$  of N. W.  $\frac{1}{4}$  sec. 36. Thence south 40 ch. set cor for the S. E. cor N. W.  $\frac{1}{4}$  of S. W.  $\frac{1}{4}$  sec 36. Thence returned to N. W. cor S. W.  $\frac{1}{4}$  S. W.  $\frac{1}{4}$  sec 36 and set corner.

May 6 & 24 - 1911.

D. V. F. Reid Co. Surveyor.