

John Brosman - Survey

Commenced at the corner to sections 29, 30, 31 & 32 T₄S, R₂₉E, which corner is marked by a rock standing against a crib of rocks at the corner of fences running west and south from the corner.

Thence North, 40 ch. the $\frac{1}{4}$ rock, 80.08 ch. intersect E & W, line 14 lks west of corner to sections 19, 20, 29 & 30 same T₄S. Returned to the $\frac{1}{4}$ corner between Secs, 29 & 30 and set the temp stake N. 4 lks and east 7 lks. Dug hole $3\frac{1}{2}$ ft. deep. Deposited broken glass and reset the government rock marked $\frac{1}{4}$ for the corner rock. Dug pits 5 ft N. & 5 ft S. of corner. Made deposits of glass 4 ft E. & 4 ft W. of corner for references.

June 1st 1911.

D. V. F. Reid - Co. Surveyor.