

L. D. (Roy) Neil - Survey.

Commenced at the $\frac{1}{4}$ corner between secs. 21 & 28 T₁N. R. 27 E. T₁W. where I dug and found the charcoal, as per field notes, and which corner I marked more permanently as described in Record of Lost, obliterated and re-established corners P. 8. Thence S. $89^{\circ}-59'$ E., 38.10 ch. E. bank Butter Creek. 39.80 Set temp stake for corner secs 21, 22, 27 & 28. No trace of original corner. Thence East. 40.26 ch. Dug in slight mound, found charcoal. Described this corner in Record of corners P. 8. From the temp cor to secs 21, 22, 27 & 28 same T₁. I ran South. 40.04 ch. Dug, found charcoal deposit as per field notes. Marked this corner in Record of corners P. 9. Again from the temp cor to secs. 21, 22, 27 & 28 I ran N. 40.14 ch. a point 28 lks E of $\frac{1}{4}$ cor which we found - the charcoal deposit as per field notes. Marked this corner as per Record of corners P. 8 & 9. Returned to temp. corner to secs 21, 22, 27 & 28 which proves to be the true corner, Dug hole $2\frac{1}{2}$ ft deep & as per Record of corners P. 9.

Mar. 26 & Apr. 8 1912.

D. V. F. Reid County Surveyor.