

Chas Bartholomew - Survey

Commencing at the $\frac{1}{4}$ corner between secs 21 & 22 T₄N. R. 27 E. T₄M. Thence North Var 22°-00' E. 40 ch. Set temp stake for cor. to Secs 15, 16, 21 & 22. No evidence at all of the location of this corner. Thence East, 40.46 ch. Dug in slight hump & found charcoal as per field notes. Marked this corner as per Record of Corners P. 9. Returned to temp cor to Secs 15, 16, 21 & 22 same T₄N. Thence North 40.16 ch. point 18 lks W. of corner. Dug, found charcoal deposit. Marked this corner as per Record of corners P. 10. The correction for the temp. cor to Secs. 15, 16, 21 & 22 is 8 lks N. & 9 lks E. Returned to this temp corner Dug & dug over a quarter of an acre altogether & finally found the charcoal deposit in the presence of Chas Bartholomew, L. D. Neill, Al. Martin & Pat Rork. This deposit of charcoal is 40.21 ch. N of the $\frac{1}{4}$ corner bet. Secs. 21 & 22 and 2 lks E. of straight line bet $\frac{1}{4}$ corners N. & S. Marked

4/11-4/14

Date 1912

Folder 1191

Page: 14C

Book: 2

this corner (to Secs. 15, 16, 21 & 22 - 1/4 N. 27 E.) as per Record of Corners P. 9. A fence N. & S. some 7 or 10 rods N. of this corner is claimed to be on the line but none could point out the location of the true corner. Elevation 1900 ft. above sea level 500 ft. above Chas Bartholomew's house.

Thence West on N. line Sec. 21 same tp. down steep hillside over Butter Creek bottom & across County Road up Butter Creek. 40 ch. set temp stake for 1/4 corner on N. side sec. 21. Dug for corner - ground level & smoothed - no trace of corner. Went to the 1/4 corner between Secs 21 & 28 tp. 1/4 N. R. 27 E. Thence West. 40.03 ch. a point 29 lks. S. of corner. Dug & found the charcoal deposit. The true course of this line is therefore S. 89° - 36' W. Marked this corner as per Record of Corners P. 10.

Thence N. between Secs 21 & 20 same tp. 40 ch. Dug & dug and found charcoal deposit at 39.91 ch on true North course. Marked this corner as per Record of corners P. 10.

Thence North. 40.09 front 10 lks N. of corner. Dug, found charcoal deposit. Marked this corner (the N. W. cor sec 21) as per Record of Corners P. 11.

Thence East. Cited from this corner to the mound at N. E. corner the true course being S. 89° - 57' E. Set flag at 40 ch. near 1/4 cor on N. side Sec. 21. Dug and found charcoal deposit 40.08 ch N. of N. E. corner. The North line Sec. 21 is 79.94 ch. & 1/4 cor is 4 lks N. of straight

4/11-4/14

Date 1912

91

Page: 15A

Thence East, Cited from this corner to the mound at N.E. corner, the true course being S. 89°-57' E. Set flag at 40 ch. near $\frac{1}{4}$ cor on N. side sec. 21. Dug and found charcoal deposit 40.08 ch. N. of N.E. corner. The North line Sec. 21 is 79.94 ch. + $\frac{1}{4}$ cor is 4 lks N. of straight line between sec. corners. Marked this corner as per Record of corners P. 11. Hundreds of thousands of sheep, cattle + horses have been driven over this charcoal deposit which is not more than 4 or 6 in. below the surface, yet it remains a perfect witness of the true situs of the original government corner. Nothing better, for the dishonest miscreant, not knowing its location, cannot remove it from its original location.

From the quarter section corner on the north line of said Sec. 21 I ran South setting temp stakes at 20 and 40 ch. Intersected South line of sec 21 - 9 lks. N. of corner. The correction for course therefore is at the 20 ch set temp stk over E. $2\frac{3}{4}$ lks and at the center sec 21 set temp stk over $4\frac{1}{2}$ lks to E.. From the $\frac{1}{4}$ cor on the N. side Sec. 21 I ran E. sighting to the flag on the $\frac{1}{4}$ cor. on the E. side Sec. 21. Intersected the temp. center line from N. to S. 20 lks S of the temp. stk. Set temp stk. over E. $4\frac{1}{2}$ lks + 20 lks S. for the corrected + true center of sec. 21. Established corner as per Record of Corners P. 11 + 12. At the N.W. cor. of S.W. $\frac{1}{4}$ of N.E. $\frac{1}{4}$ set the temp. stake E. $2\frac{3}{4}$ lks and S. 10 lks. Dug hole set rock 14X 10X8 marked C.D. for corner and old wagon bolter stake against

4/11-4/14

1191

Folder _____, Date 1912

16A

Book: 2, Page: _____

it. Made charcoal deposit 2 ft deep 10 lks. N.E. and a deposit of horseshoe, glass & tin cans S.W. 10 lks. & two ft. deep.

From thence ran S. 89°-57' E. being the course of the north line of Sec. 21 and also of the E. & W. center line and at 39.99 1/2 ch. Set the corner, being the N.W. cor S.E. 1/4 N.E. 1/4 Sec 21. Set up stone marked C S on rim rock. This is Roy Neil's N.E. corner.

From the center corner of Sec. 21 same th. ran S. 89°-57' E. 39.94 1/2 lks. Set rock 14X16X10 marked C.S. for N.E. cor N.W. 1/4 S.E. 1/4 Sec 21, being Roy Neil's S.E. corner.

In the finding of the eight charcoal corners in the chas. Bartholomew survey there were present L. D. (Roy) Neil, Al. Martin, Chas. Bartholomew & D. V. J. Reid

Apr. 11 to 14 - 1912.

D. V. J. Reid Co. Surveyor.