

Lafe Pauland & R. W. Owen - Survey.

Commencing at the $\frac{1}{4}$ corner bet. Secs. 2 & 3 - 5 S. R 27 E. N. W. Thence North, 20 ch. Yellow Pine blazed for line tree, 73.30 Creek, 77.75 ch. corner. Established or renewed this corner as per Record of Corners P. 13. Thence East, on Gp. line, 2.90 ch. Creek, 3.60 to S. E. cor Sec. 34. Found no stake or witness trees. Set temp stake, 43.60 Searched for $\frac{1}{4}$ cor on S. side Sec. 34 but found no trace of it. found blazed trees along this line so far, but not on a true line or a straight line, 80.64 to N. W. cor said Sec. 3. At which found rock 16 X 14 X 12 lying on top ground. Rock not marked. Found from witness trees rock to be in 3 ft of point determined by witness trees. Dug hole & rolled rock into it to await the action of future surveyors.

From the N. E. cor Sec. 3 - 5 S. 27 E. Iron N. 31° 10' W. 6.96 ch. to E. line Sec. 32 - 45, 27 E. at a point 3.95 ch. N. of S. E. cor Sec. 32, 40 ch. set temp stk. 80.19 point 23 lks E. of N. E. cor Sec. 32 said Gp. Found

Folder 1193, Date 04/1912
03/1912

Book: 2, Page: 16C & 17A

rock as described in Record of Corners P. 14

Returned to temp. stk on E. side Sec. 34 set it over. $9\frac{1}{2}$ lks N. and $11\frac{1}{2}$ lks W. Dug hole &c as per Record of Corners P. 14.

Thence West. Down steep hill, up steep hill & over ridge. 41.22 wagon road to Hamilton Ranch. 42.77. Creek. 46 Andy Stevenson's old cabin S. 2 ch. 60 ch. set temp. stake. 63. ch ascend 67. ch top ridge. Precipitous canyon ahead. Did not run further on this line.

From the temp stake, 2" line above, ran South 40.58 ch. the tp. line at a point 2.03 ch. W. from the N.W. cor N.E. $\frac{1}{4}$ N.W. $\frac{1}{4}$ Sec. 3-58-27 E.

The corner for the 40 on N. of tp line is 3.40 ch. W. of the corner for the 40 on S. side tp line, therefore set over W. 1.37 ch. further W. for R. W. Owen's west line on the N. side of the tp line & set a corner. Dug hole, set rock marked C.S., built mound rocks from which Pine 30 in line tree blazed E. & W. is W. 2.79 ch. & Pine 32 in. North 1.73 ch.

Survey stopped here. not continued
Apr 28 to May 7 - 1912

D. V. F. Reid Co. Surveyor.