

Claud & Emerson Keithley Survey

Commencing at the corner of Secs. 3, 4, 9 & 10 Twp. 4S Range 24 E.W.M. I ran East 79.27 chains to corner of secs. 2, 3, 10 & 11, thence returned West 39.63 chains and set temporary stake for $\frac{1}{4}$ corner between secs. 3 & 10.

Commencing at $\frac{1}{4}$ corner between secs. 10 & 11, I ran West 79.44 chains to $\frac{1}{4}$ corner between secs. 9 & 10, thence returned East 39.72 chains and set stone 16-8-6 inches marked CS with pits, of fine coal 16 inches deep, 10 links to the NE, NW, SW & SE. for center of section 10 thence South 20 chains and drove small stake for NE corner of SE $\frac{1}{4}$ of SW $\frac{1}{4}$ of sec. 10.

Returning to center of sec. 10, I ran North 40 chains and set flat stone 16-12-2 ins. marked CS, with pits, of fine coal, 16 inches deep at a distance of 10 links from the corner, for $\frac{1}{4}$ corner between secs. 3 & 10.

Mar. 13 - 14 1913.

Loy M Turner Co. Surveyor.

Folder 1200, Date 3/13-14, 1913

Book: 2, Page: 20B