

**NOTICE OF ESTABLISHMENT OF BOUNDARY.**

To Frank Saling, B. P. Doherty, T. M. Keller of Portland, Oregon, Oregon-Dakota Land Co. of Oregon, W. F. Honey, agent, Gresham, Oregon:  
You and each of you will take notice that on May 1st, 1930, I will officially establish the south boundary of the north half of the south half of Section 15, Tp. 1 N., R. 26, E. W. M.  
H. TAMELYN, County Surveyor.  
Dated at Heppner, Oregon, April 8, 1930.  
Date of first notice April 10, 1930.  
Date of third notice April 24, 1930.

**Affidavit of Publication**

STATE OF OREGON, County of Morrow,—ss.

I, Vawter Crawford, being first duly sworn, depose and say that I am the Printer (printer, foreman of the printers, principal clerk, publisher, or business manager) of HEPNER GAZETTE TIMES, a newspaper of general circulation printed and published at Heppner, in the aforesaid county and state, as defined in Section 58, Oregon Laws, that Notice of Establishment of Boundary a printed copy of which is hereto annexed, was published in the entire issue of said newspaper for three successive and consecutive weeks in the following issues: April 10th, 17th and 24th, 1930.

Vawter Crawford  
Subscribed and sworn to before me this 2nd day of May, 1930, 1920  
Joe J. Mayo  
Notary Public for Oregon.  
(My Commission expires May 31, 1931).

Folder 1208, Date 4/1930  
Book: 2, Page: 23A

OFFICIAL SURVEY

for

B. P. DOHERTY  
 Establishment of the South Boundary of the N 1/2  
 S 1/2 Section 15, T. 1 N., R 26 E. W. M.

Petition having been recieved from B. P Doherty to establish the South boundary of the North one half of the South one half of Section 15, T 1N. R 26 E. W. M. I notified the parties concerned by personal service and by advertisement in the Heppner Gazette Times, a newspaper published in Heppner, Oregon, that on May 1, 1930 I would officialy survey and establish the said boundary.

On May 1, 1930 I took to my assistance Dale Bleakman, Percy Bleakman and Lavon Hiatt, who were duly sworn to perform the duties of chainmen and proceeded with the survey.

I take for a starting point a mound of rock with a part of an old axe handle for a stake which I assume to be the East one quarter corner of Section 15 and search for evidence of the original corner but find none, from thence I run;

North (Mag Var 21°40') 39.90 ch. a Corner to Sections 10-11-14-15 which I identify by charcoal as described in the original field notes. I mark the corner with a large stone marked with 11 notches on the East side and 1111 notches on the south side and the letters C. S. 30. From thence I run;

N 0°57'E 40.27 Ch the one quarter corner on the East side of Section 10 which I identify by an unmarked stone and charcoal. I mark the corner with a large rock with the mark 1/4 and the letters C. S. 30.

I return to the assumed one quarter corner on the East side of Section 15 from thence I run;

S 0°33'W 39.90 ch and set hub for temporary corner to Sections 14-15-22-23 and search but can find no evidence of the original corner. I run thence;

S 0°47'W 40.30 ch to the one quarter corner on the East side of Section 22 which I identify by a mound of rock and charcoal. I mark the corner with a large rock with the mark 1/4 and the letters C. S. 30.

Folder 1208, Date 5/1930, Page 23A  
 Book 2

I return to my temporary corner to sections 14-15-22-23 and run thence;

S 89°18'E (Mag. Va. 21°40') 39.98 ch to the one quarter corner on the North side of Sec. 23 which I identify by a fence corner and charcoal as described in the original Notes. I mark corner with rock.

I return to my temporary corner to Sections 14-15-22-23 and run thence;

N 89°43'W 40.33 ch and find the North one quarter corner of Section 22 which I identify by the remains of old stake. I mark the corner with a large rock marked 1/4 and the letters C. S. 30.

I return to the SE corner of Section 15 and establish the corner to Sections 14-15-22-23, 20 links South and 17 links West of the temporary corner, from whence are the various courses and distances;

N. 0°48'E 40.10 ch to the assumed 1/4 corner on the East side of Section 15.  
N 89°10'W 40.16 ch to the South 1/4 corner of Section 15  
S 89°02'E 40.15 ch to the North 1/4 corner of Section 23.  
S 0° 28'W 40.10 ch to the East 1/4 corner of Section 23.

As the assumed 1/4 corner on the East side of Section 15 has apparently been accepted as a corner for a considerable time and old fence lines have been built with reference to it and it is nearly mid way between the two section corners I grant it to be the position of the original corner and mark it with a stone 6 x 8 x 18 inches with the mark 1/4 and the letters C. S. 30 and deposit broken glass and charcoal.

From the 14 corner on the South side of Section 15 I run;

N 89°00'W (Mag Var 21°40') 39.97 ch to the corner to Sections 15-16-21-22 which I identify by the remains of an old stake and charcoal. I mark the corner with a large rock marked 111 notches on the East side and 111 notches on the South side with the letters C. S. 30. from thence I run;

N 0°32'E 40.03 ch to the 14 corner on the West side of Section 15 which I identify by the remains of an old stake and charcoal. I mark the corner with a large rock marked 1/4 and the letters C. S. 30, from thence I run;

N 0°09'E 39.95 ch to the NW corner of Section 15 which I identify by the remains of an old stake. I mark the corner with a large rock with

Folder 1208, Date 4/1930  
Book: 2, Page: 23A

1111 notches on the South side  
and 111 notches on the East  
side and the letters C. S. 30.  
From thence I run;

S 88°50'E (Mag. Var. 21°40') 40.15 ch. to the North 1/4 corner  
of Section 15 which I identify  
by the remains of old stake and  
charcoal. I mark the corner with  
a large rock with the mark 1/4  
and the letters C. S. 30.  
From thence I run;

S 89°20'E 40.10 ch to the N. E. Corner of Section 15.

SUBDIVISION OF THE SOUTH HALF OF SECTION 15.

Begin at the SE corner of Section 15 and run;

N 0°48'E 20.05 ch. and set a large rock marked 1/16

Begin at the SW corner of Section 15 and run;

N 0°32'E 20.015 ch. and set a large rock marked 1/16

*H. Tamblyn*  
H. Tamblyn  
County Surveyor

May 8, 1930.

You have thirty days in which to file an appeal.

Folder 1208, Date 5/4/1930  
Book: 2, Page: 23A