

Nov. 25th 1927

Land Survey for Michael
Kenny and T.J. O'Brian

Set up on Sec. Corner Common to
Secs. 22-23-26 & T. 11-S-R-27 East
and ran East 40 chains and set stake
marked $\frac{1}{4}$ Corner thence 40 chains
to Corner Common to 23-24-25 & 26
missed Corner 46 Links North
Offset stakes and correct back
50 Ch. off. 40 Links - 40 Ch. off. 33 Links
30 Ch. off. 24 Links - 20 Ch. 16 Links
18 Ch. 14.4 Links 11 Ch. 8.8 Links 7 Ch.
5.6 Links

Thence south 20 Chains thence
East 20 chains and set stake

Nov. 26th 1927

Set up on $\frac{1}{4}$ Corner on
Range line between R. 26 & 27
between Sec. 25 & 30
and ran west 60 ch. and set stake
for $\frac{1}{4}$ - $\frac{1}{4}$ Corner Thence North
20 Chains and hit 50 North and
22 Links west of $\frac{1}{4}$ - $\frac{1}{4}$ Corner

Ralph Harris
T.J. O'Brian { Chairman
Joe Kenney }

Ralph Harris

2 Days + Night work 14 15
1 60

23 22 40c
26 27

2000 Rock found
2000 Rock found
2000 Rock found

Michael Kenny

Corner found
 $\frac{1}{4}$ Corner Not found

2000 set stake
2000 set stake
2000 set stake
2000 set stake
60 ch.