

50 chains West and 5.88 chs.

North of the NE corner of  
Section 25 Tp 5 N R 26 E W.M.,  
Said point being in the  
center of the road South  
of the C.W.R. & N.R.R. set stone  
15 x 10 x 5 marked R, also set  
post marked R, 26 links  
North of above named point  
and being on line with

Telephone pole line, thence  
N 87° 52' W along road 66 chs,  
set A stone 26 V links South of  
line, thence North 72 links  
to center of road, set A stone  
North 30 links at corner of  
RR fence at road crossing,  
thence N 87° 52' W 13.28 chs.  
set 1 M post North of line  
25 ft. South of RR fence

thence N 87° 52' W 65.26 chs

Set A stone North 20 ft. thence  
South 12.85 the W corner  
of Sec. 26 Tp 5 N R 26 E W.M. thence  
South 1.89 ch, set 2 M. Post  
West of line 30 ft. Thence South  
80 ch. set 3 M post West  
of line 30 ft. Thence South  
78.11 ch. to corner of sections  
34, 35 - on Tp 5 line of between  
Tps. 4 and 5 North, the first  
Standard Parallel North thence  
South 1.89 chs. set 4 M Post  
30 ft. West of line, thence  
South 2.11 chains set A stone  
20 ft East of line. thence  
S 42° 26' W <sup>15</sup> 39 chs. to a point  
15 chs. South of corner to Sec.  
2 and on Tp. line between 4 and  
5 North, thence South

set A stone West 30 ft

thence South 62.50 set

5 M post. 30 ft West of line

thence South 80 chs. set 6 M

post 30 ft West of line, thence

South 60 chs. set 7 M post

(6.5 chs North Sec. corner) 30

ft West of line. South 80

chs. set 8 M post 30 ft

West of line thence South

80 chs. set 9 M post 30 ft.

West of line. South 80 chs.

set 10 M post 30 ft West

of line. thence South

80 chs. set 11 M post 30 ft

West of line. thence

South. 80 chs. set 12 M post

30 ft West of line, thence

South 80 chs. set 13 M post

30 ft West of line, thence

80 chs set 14 M post 30 ft

West of line, thence South

80 chs thence South 80 chs

intersect channel running

North and South for 50 chs,

(would advise to keep road

West of ditch.) South 80 chs

set 16 M post 30 ft West of

line, South 32 chains center

of channel 60 ft wide, 80

ft. set 16 M post 30 ft

West of line. South 76

chains, set granite A stone

130 ft East of line.

Thence S 24° 33' E 4 chs set

17 M post board, 16 chs

set A stone 30 ft East

of line. thence South

40 17' W 64 chs, set 18 M

post 30 ft West of line

78

Book 3

Thence South  $40^{\circ} 17' W$

9.66 ds to corner of Sec.

10-11-14-15<sup>+</sup> T<sub>2</sub> N R 26 E W M

set stone marked R.C.  
for terminal of road.