

Nov. 2, 1923
 Survey for Key Broom
 Part Connelley

Set up on 1/4 sec 20th sec. 1 & 8
 of T. 8 R. 26 E. 11 N.
 Right to line corner
 2 1/2 miles south which
 I know from previous
 survey to be on line, and
 assume the line to be
 due east.

Thence turn due east on
 random line

11.75 = center of County Road

20.00 set temp 1/4th cor.

40.00 ch set temp 1/4 cor for
 center of Sec. 8 cor
 top of ridge

60.00 set temp 1/4th cor

80.80 ch part 7 & 8 fence
 could find no trace of 1/4 cor

A running of stone fence located in
 ground with large hole in center
 could find no mark on rock.
 rock at top of Rock cut, fence
 running north and west.

Returned on true line
 and set 20.20 set stakes for
 NE cor. of NW^{1/4} of A 20,
 flagged true line south
 Return to SW corner true
 line and set 60.60 ch
 set stakes for NW cor
 of NE^{1/4} of SW^{1/4}
 Thence run south 20 ch
 set stakes for SW cor
 of NE^{1/4} of SW^{1/4}
 Thence East 20, 20 ch set
 stakes for SE cor. of NE^{1/4} of SW^{1/4}
 Thence south 20 ch
 and set the 1/2 cor
 between Sec. 8 & 17,
 Sp. 4 & 5 P 26 E.