

April 3rd 1925.

Survey for H. Crump

10 Sec. 12, T₁S. R₂₇E. W.M.

Set up in Turner Corner at 1/4 cor.

Rt. Secs. 13 & 14, T₁S. R₂₇E. W.M.

Flag to SE cor. of 14,

Stand and chain North

40.00 ch. E X W fence, 24' (As East)

Fence corner.

Culinary Stone corner

North

15.25 stn ke

20.00 set lamp pole cor.

34.00 Raring

40.00 ch. Find the 1/4 corner at a point

1.15 ch S. 34° W. a stone ASIDE

set in ground, small mound of

rock along side, 3 ft. to the west

39.05 ch the 1/4 Sec cor bet S. cor. 11 & 12

at a point 64 ft. N. Ks West of

Road on line

Renew mound about corner

11.15

S. 34° W. 1.15

8.29

1.15

41.45

8.29

95.335

.059

2.795

5.59

55.9

64.285

21

4

64

Continue same course

State on Ridge

50.55 station Ridge. set 70 Lks West

80.10 ch. Set Temp Cor to Secs 1-2-11-12
continue same course120.00 Find 1/4 Cor. set Secs 1 & 2
a stone 4x8x16, mark 1/4, small corner
Penny mound mark cross top of rock119.72 Find Kerr at point 96 lks West
of line.A 79.38 1/2 Set corner to Secs 1-2-11-12
at Point 80 Lks West of Random line

S 73° 45' W. 100

Lat 28 lks

Dep. 96 lks

$$\begin{array}{r} 96 \\ 64 \\ \hline 2 \sqrt{160} \\ 80 \end{array}$$

$$\begin{array}{r} 80 \\ 64 \\ \hline 16 \end{array}$$

60

$$\begin{array}{r} 119.72 \\ 39.05 \\ \hline 2 \sqrt{180.67} \\ 40.33 \frac{1}{2} \\ 39.05 \\ \hline 79.38 \frac{1}{2} \end{array}$$