

July 10, 1926

Survey for 1st Nail Bank

Frank Monahan.

Jim Higgins

John Kelley Axmen

W.P. Mahoney.

Frank Donohue Chairman

Relocate Stake to Secs 33-34

Tp 4SR 28E by Measurement

from Witness Trees, both of
which are found.

Measured East Abut but failed

to find Closing Corner 20

Secs 34 & 35 SR 28E. Both

located on old bearing

tree, others having been

destroyed by Road builders and

mine activities.

Run Random Line West 1/23-

and along old blazed line

39.80 find 1/4 c. around of Sandstone

with blazed tree north, as per field

notes and blazed rotten stump of

fir tree south of line, at field

note distance

Relocate Corner by setting a Sand Stone
8X11X15, AKd + on top 11. on East & West
edges, 11.11 on South face, CS on North face
Set middle of Rock around corner Stone