

Oct, 3, 1924

Survey 17 Sec 15, T13R25E.

Get IDN GUNSET + MAY Halverson

MAY Halverson, flagman

Fred L. Koontz, Chainman

Clyde Shriver, "

Setup on Corn to Sec 05. 9-10-15-16

TPI5 R 25E. Which is a stone

8x12x22, properly marked in mound
of stone, about 150 ft east and above
bottom of draw.

Ruin random line East

20.49 sp. to fence

40.00 set lamp for car.

40.49 find old 4 year stone base on ground

30 Links North of random line

41.23 ch. N45 South fence at a point 59 links north of

52.28 stake

56.75 fence at west side of grain field

80

60.00 ch. NE corner of ~~wood~~ 11-14-15.

52.28 x 65

$$\begin{array}{r} 52.28 \\ 26140 \\ \hline 51768 \\ 343820 \\ \hline 343820 \\ 20780 \\ \hline 345898 \end{array}$$

$$\begin{array}{r} 2076 \\ 543820 \\ 22304 \\ \hline 20780 \end{array}$$

 replace 4 cm at point 50 LKS N 49° 40' E and build
mound of rock around.

fence corner

mistake 42 LKS North

142

Book 18

80.00 ch. set temp cor to Sees 10-11-14-15

from which point we find the Sec Cor
at a point N. $49^{\circ}40'E$ 1.00 ch.

80.76 ch. the cor to Sees 10-11-14-15 at a point
45 fks. North of Random Line

Setup on NE cor of NW $\frac{1}{4}$ of NE $\frac{1}{4}$ Sec 15
Run South

20.00 set post for $\frac{1}{4}$ $\frac{1}{4}$ Cor

Thence P. S. $45^{\circ}00'W$.

26.28 to SW cor of SW $\frac{1}{4}$ of NE $\frac{1}{4}$ $\frac{1}{4}$ cor.
at 25.28 fence running S. $21^{\circ}41'W$

Setup on center of Section 15
and run South

20.00 ch set post for $\frac{1}{4}$ $\frac{1}{4}$ cor at NE end of
SET of SW $\frac{1}{4}$

143

Book 18

57 fks. west of edge of draw.