

Oct. 19-16.

At corner to Tps. 1-2 S
 Rs 25-26 E found mound
 with pits slightly discernible
 but no stake visible.
 I re-established corner
 by setting stone 30 X 12 X 8
 with a large end beneath
 the surface. Stone not
 marked. Re-dug pits and
 made mound over stone.

Set stone 15-12 X 10 - 20 lbs.
 North of T₁ corner for 40
 corner.
 S 89° 54' E 39.33 chains
 from T₁ corner set post
 in mound marked by an
 west face for $\frac{1}{4}$ corner
 on South side of sec. 31.