



NARRATIVE:
 This Survey was performed at the direction of the Morrow County Court. The purpose was to establish the Township Line which is the East Boundary of the Naval Bombing Range Reservation Property. Bombing Range Road lies just inside the township line and is maintained as a County Road on naval property. The Township Line along the Naval Boundary was re-established according to the best information recreated from the local Found Section Corners. Both the GLO Record and the Dependent Resurvey by Gould in 1939 were used to establish lost, disturbed, or obliterated corners. Lost Monuments were re-established according to Chapter V of the 1973 BLM Manual of Surveying Instructions. The Basis of Bearing was according to Gould's survey in the South portion of Township 3 North as shown. This survey was performed with Trimble 4800 RTK receivers with an occupation time set to achieve +/- 0.02' at each station. All locations were occupied with the Base Station at two locations and with the average of each result used to establish angles and distances.

- LEGEND:**
- ⊕ FOUND SECTION MONUMENTS as Noted
 - ◆ SET SECTION MONUMENTS as Noted
 - { 000 } GLO RECORD
 - { 000 } RECORD Gould, 1939 Dependent Resurvey GLO

RECORD of SURVEY for MORROW COUNTY
 Townships 2 North, 3 North, & 4 North,
 Ranges 25 & 26 East, W.M.
 Bombing Range Road
 Morrow County, Oregon

REGISTERED PROFESSIONAL LAND SURVEYOR
RONALD V. MCKINNIS
 JAN. 23, 1990
 2431
 Expires 12-31-04

RECEIVED BY
Morrow County Surveyor
 Date 01/03/05
 Rec'd By RJM
 No. D-1410-M

0 500 1000 2000 3000
 SCALE 1" = 1000 Ft.
 Rev. 11-30-04
 ENGINEERING - LAND SURVEYING - WATER RIGHTS
R. V. MCKINNIS ENGINEERING
 79980 Prindle Loop Road
 Hermiston, Oregon 97838
 (541) 567-2017