



- SET 5/8" X 30" STEEL REBAR WITH A PLASTIC CAP MARKED COPPOCK LS 2850.
- MONUMENTS FOUND AS NOTED.
- ⊙ GOVERNMENT CORNERS AS NOTED.
- ⊕ COMPUTED ALIQUOT PART CORNERS.
- *** EXISTING FENCES.
- (000) OF RECORD
- EXISTING CITY WATER LINE AS LOCATED BY CITY.

SURVEYORS NARRATIVE:

THE PURPOSE OF THIS SURVEY IS STEP ONE OF A THREE PART PROCESS TO CREATE NEW CEMETERY PLOTS FOR THE HEPPNER CEMETERY MAINTENANCE DISTRICT BOARD. THIS SURVEY WAS PREPARED AND FILED TO SIMPLIFY THE FUTURE PARTITION AND SUBDIVISION PLATS WHICH WILL BE BASED ON THIS SURVEY.

THIS SURVEY WAS PERFORMED USING LOCUS SINGLE FREQUENCY STATIC GPS RECEIVERS, HAVING A STANDARD ERROR OF +/- 5MM + 1 PPM TIMES THE BASE LENGTH, AND A NIKON DTM-430 TOTAL STATION HAVING STANDARD ERRORS OF +/- 00°00'03" ANGULAR AND +/- 3MM + 3 PPM TIMES THE DISTANCE. ALL MONUMENTS SHOWN AS FOUND WERE VISITED DURING THE COURSE OF THIS SURVEY.

ALL BEARINGS AND DISTANCES SHOWN AS MEASURED ARE TRUE.

RECEIVED BY
Morrow County Surveyors
 Date AUG 27 2007
 Rec'd By SKB
 No. 1510-C

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

John L. Copcock
 OREGON
 JANUARY 20 1998
 JUDSON L. COPPOCK
 2850

RENEWAL DATE: DEC. 31. 2007

BOUNDARY SURVEY FOR:
 THE HEPPNER CEMETERY MAINTENANCE DISTRICT.

COPPOCK SURVEYING 30 JULY 2007
 P.O. BOX 495 541-676-8750
 HEPPNER, OR 97836 FAX 676-8753
 Job No. 0806382