



NARRATIVE:

THE PURPOSE OF THIS SURVEY IS TO SURVEY THE LOCATION OF A P.V.C. PIPE WHICH THE WEST EXTENSION IRRIGATION DISTRICT RECENTLY INSTALLED IN PLACE OF A CONCRETE LATERAL AND TO SHOW THE IRRIGATION EASEMENT ON THE FOLLOWING PARCELS: DERRICK (DEED M-48399), FOX (DEED 2003-7016), AND DOONEY-RODRIGUEZ (DEED 2000-2551).

THE BOUNDARY BETWEEN FOX AND DOONEY-RODRIGUEZ IS "THE NORTH SOUTH LATERAL" WHICH WAS A CONCRETE DITCH WHICH WAS REPLACED BY A P.V.C. PIPE.

I FOUND A 3" ALUMINUM CAP (STAMPED 10-2, 1987, U.S ARMY CORPS OF ENGINEERS WITH A PLASTIC POST MARKED "BOUNDARY") 1 FOOT EAST OF WHERE I COMPUTED THE LOCATION OF THE NORTH 1/4 CORNER OF SECTION 1, T 4 N, R 26 E, AND USED IT AS THE 1/4 CORNER. THE NORTHWEST CORNER OF THE ORDNANCE ARMY BASE IS SAID 1/4 CORNER.

I USED A TOPCON HIPER+ G.P.S. TO CONDUCT THIS SURVEY AND THE BEARINGS ARE BASED ON THE LOCALIZATION OF THE W 1/16 & S 1/4 OF SECTION 36, T 5 N, R 26 E, AS SHOWN ON MY SURVEY CS#1466.

REGISTERED PROFESSIONAL LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
9 5 1
RENEWS 12/31/2015

DETAIL

SCALE 1"=150'

DETAIL-DETAIL

NO SCALE

RECEIVED BY
Morrow County Surveyor
Date: 2-28-14
Rec'd By: S.K.H.
No.: 2014-1694C
Folder No.: 1694

LEGEND:

- FOUND MONUMENTS AS NOTED
 - SET 5/8"X24" OR 30" IRON REBAR WITH PLASTIC CAP #951
 - SET PK NAIL
 - COMPUTED LOCATION
- [000] OF RECORD, 1939 G.L.O. SURVEY BY GOULD
(000) OF RECORD, MY CS#1466

SURVEY FOR WEST EXTENSION IRRIGATION DIST. IN NW 1/4 SEC. 1, T 4 N, R 26 E, & SW 1/4 SEC. 36, T 5 N, R 26 E, W.M., MORROW COUNTY, OR 01/29/2014 JOB# S1401003 EDWARDS SURVEYING P.O. BOX 763 541-567-3336 HERMISTON, OREGON 97838 DRAWN BY JMC